

AA-869

Odenton Survey District
Odenton

Mid-19th through
Early 20th centuries

Public and Private

The Odenton Survey District is located within the older community of Odenton in northwest Anne Arundel County. It consists of 87 contributing resources, including dwellings, churches, a school, Masonic halls, railroad facilities and other structures, most of which were built in the late 19th and early 20th centuries.

The historical development of Odenton is closely linked to the development of rail transportation connecting Washington, D.C., Baltimore and Annapolis. The location of Fort George G. Meade in 1917, just west of Odenton, also served as an impetus for Odenton's further growth.

Maryland Historical Trust State Historic Sites Inventory Form

Survey No. AA-869

Magi No.

DOE ☒ yes ☐ no

AA-727 Frank Watts House
(within Odenton Survey
District)

1. Name (indicate preferred name)

historic

and/or common Odenton Survey District

2. Location

street & number primarily Odenton Rd. (Rt. 677) and others ☐ not for publication

city, town Odenton ☐ vicinity of ☐ congressional district 4th

state Maryland ☐ county Anne Arundel

3. Classification

Category	Ownership	Status	Present Use
<input checked="" type="checkbox"/> district	<input type="checkbox"/> public	<input checked="" type="checkbox"/> occupied	<input type="checkbox"/> agriculture
<input type="checkbox"/> building(s)	<input type="checkbox"/> private	<input type="checkbox"/> unoccupied	<input checked="" type="checkbox"/> commercial
<input type="checkbox"/> structure	<input checked="" type="checkbox"/> both	<input type="checkbox"/> work in progress	<input checked="" type="checkbox"/> educational
<input type="checkbox"/> site	Public Acquisition	Accessible	<input type="checkbox"/> entertainment
<input type="checkbox"/> object	<input type="checkbox"/> in process	<input type="checkbox"/> yes: restricted	<input type="checkbox"/> government
	<input type="checkbox"/> being considered	<input type="checkbox"/> yes: unrestricted	<input type="checkbox"/> industrial
	<input checked="" type="checkbox"/> not applicable	<input checked="" type="checkbox"/> no	<input type="checkbox"/> military
			<input type="checkbox"/> museum
			<input type="checkbox"/> park
			<input checked="" type="checkbox"/> private residence
			<input checked="" type="checkbox"/> religious
			<input type="checkbox"/> scientific
			<input checked="" type="checkbox"/> transportation
			<input type="checkbox"/> other:

4. Owner of Property (give names and mailing addresses of all owners)

name Multiple Owners

street & number ☐ telephone no.:

city, town ☐ state and zip code

5. Location of Legal Description

courthouse, registry of deeds, etc. Anne Arundel County Courthouse ☐ liber

street & number Church Circle ☐ folio

city, town Annapolis ☐ state MD

6. Representation in Existing Historical Surveys

title Anne Arundel Co. Historic Sites Survey (AA-727, 743, 751, and 752)

date 1978 and 1980 ☒ federal ☒ state ☒ county ☐ local

depository for survey records Maryland Historical Trust

city, town Annapolis ☐ state MD

7. Description

Survey No. AA-869

Condition		Check one	Check one
<input checked="" type="checkbox"/> excellent	<input type="checkbox"/> deteriorated	<input checked="" type="checkbox"/> unaltered	<input checked="" type="checkbox"/> original site
<input checked="" type="checkbox"/> good	<input type="checkbox"/> ruins	<input checked="" type="checkbox"/> altered	<input type="checkbox"/> moved date of move _____
<input checked="" type="checkbox"/> fair	<input type="checkbox"/> unexposed		

Prepare both a summary paragraph and a general description of the resource and its various elements as it exists today.

Description

The Odenton Survey District is located within the older community of Odenton in northwest Anne Arundel County. It consists of 87 contributing resources, including dwellings, churches, a school, Masonic halls, railroad facilities and other structures, most of which were built in the late 19th and early 20th centuries.

Old Odenton is clustered around the intersections of the Annapolis and Elkridge Railroad with the Baltimore and Potomac Railroad and the Baltimore and Washington Electric Railroad. The Annapolis and Elkridge Railroad and the Baltimore and Washington Electric line became the Washington, Baltimore and Annapolis Railroad in 1908. The Baltimore and Potomac Railroad became part of the Pennsylvania Railroad, and is currently used by Amtrak. The Baltimore and Washington Electric Railroad tracks, which form the east boundary of the survey district, were removed after the Washington, Baltimore and Annapolis ceased operation in 1950; the roadbed is still visible in Odenton. The Annapolis and Elkridge tracks were also removed east of the intersection of the Baltimore and Potomac Railroad (Amtrak). The old Baltimore and Potomac line (Amtrak) is the only remaining active line in Odenton, still giving definition to it as a railroad town.

Odenton Road (now Route 677) was the main east-west road through town. It has been bypassed to the north by the new Route 175, along which much new development has occurred. A present-day traveler on Route 175 would be unaware that Old Odenton still exists to the south and north of it.

The dwellings located within the survey district are predominately frame and reflect the influence of the late 19th century Queen Anne architectural style and the early 20th century Four-Square Plan, Classical Revival and Bungalow styles. The Queen Anne influence is best seen at the eclectic Frank Watts House at 1401 Odenton Road. Begun in 1881 as a two-story central passage plan house with a cross-gable roof, it was expanded several times, resulting in an interesting and picturesque composition.

Another two-story central passage plan dwelling with a cross-gable roof and later additions is the George M. Murray House at 1390 Odenton Road. It is a much simpler house in composition than the Watts House. Built in 1873, the Murray House is the oldest standing structure in Odenton.¹

The early 20th century Four-Square Plan house is characterized by a blocky, square plan and large dormers set into a steeply pitched roof. This is illustrated by 1366, 1381 and 1385 Odenton Road, to name a few.

An early 20th century Classical Revival influenced house is depicted at 1391 Odenton Road. The gable end forms the principal facade and has a wrap-around porch supported by Doric columns. The bank of windows in the attic story of the gable end is a stylized version of the classical 3-part Palladian window.

8. Significance

Survey No. AA-869

Period	Areas of Significance—Check and justify below			
<input type="checkbox"/> prehistoric	<input type="checkbox"/> archeology-prehistoric	<input type="checkbox"/> community planning	<input type="checkbox"/> landscape architecture	<input type="checkbox"/> religion
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> archeology-historic	<input type="checkbox"/> conservation	<input type="checkbox"/> law	<input type="checkbox"/> science
<input type="checkbox"/> 1500-1599	<input type="checkbox"/> agriculture	<input type="checkbox"/> economics	<input type="checkbox"/> literature	<input type="checkbox"/> sculpture
<input type="checkbox"/> 1600-1699	<input checked="" type="checkbox"/> architecture	<input type="checkbox"/> education	<input type="checkbox"/> military	<input type="checkbox"/> social/
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> art	<input type="checkbox"/> engineering	<input type="checkbox"/> music	<input type="checkbox"/> humanitarian
<input checked="" type="checkbox"/> 1800-1899	<input checked="" type="checkbox"/> commerce	<input type="checkbox"/> exploration/settlement	<input type="checkbox"/> philosophy	<input type="checkbox"/> theater
<input checked="" type="checkbox"/> 1900-	<input type="checkbox"/> communications	<input type="checkbox"/> industry	<input type="checkbox"/> politics/government	<input checked="" type="checkbox"/> transportation
		<input type="checkbox"/> invention		<input type="checkbox"/> other (specify)

Specific dates

Builder/Architect

check: Applicable Criteria: ☐ A ☐ B ☐ C ☐ D
and/or

Applicable Exception: ☐ A ☐ B ☐ C ☐ D ☐ E ☐ F ☐ G

Level of Significance: ☐ national ☐ state ☐ local

Prepare both a summary paragraph of significance and a general statement of history and support.

The historical development of Odenton is closely linked to the development of rail transportation connecting Washington, D.C., Baltimore and Annapolis. The location of Fort George G. Meade in 1917, just west of Odenton, also served as an impetus for Odenton's further growth.

In 1837, the second railroad in Maryland, the Annapolis and Elkridge, was chartered and by 1840 was in operation, connecting Annapolis with the Baltimore and Ohio Railroad's Washington branch. The junction with the Baltimore and Ohio in northwest Anne Arundel County became known as Annapolis Junction. The line ran southeast to Annapolis, giving rise to a few small towns along the way. Millersville was one of the first to be established, followed by Crownsville by 1860. A cluster of six structures in the vicinity of Odenton appears on Simon Martenet's 1860 map of Anne Arundel County.

In 1860, Oden Bowie, from whom Odenton draws its name, became the President of the Baltimore and Potomac Railroad, a newly chartered railroad which ran between Baltimore and Washington. This line, later absorbed by Pennsylvania Railroad, is the present line used by Amtrak.

In 1868, a house and station were built in Odenton on the east side of the Baltimore and Potomac tracks; Odenton was officially established. (The house and station are no longer standing.) Service began in 1872 during the final year of Oden Bowie's term as Governor of Maryland.

The Maryland Directory of 1878, as referenced in Catherine O'Malley's Odenton--The Town a Railroad Built, described Odenton as having a population of 100. Its climate was mild and healthy,

... business and land medium; not much cleared; the timbered land is a heavy growth and that yet standing is composed of chestnut, pine and oak; land is worth from \$5 to \$30 per acre and produces 10 bu. of wheat, 20 bu. of corn. Corn and tobacco crop good. The inducements to emigrants are cheap lands, one church and one public school.

Survey No. AA-869

Hopkins, G. M. Atlas of Anne Arundel County Maryland, 1878.
Martenet, Simon. Martenet's Map of Anne Arundel County Maryland, 1860.
O'Malley, Catherine L. Odenton - The Town a Railroad Built. Annapolis and St. Michaels,
Maryland; Jackson Printing, Inc., 1978
White, Roger B. "The W. B. & A. - A Short Outline of the Short Line."

Acreage of nominated property _____

Quadrangle name Odonton

Quadrangle scale 7.5

UTM References do NOT complete UTM references

Verbal boundary description and justification

List all states and counties for properties overlapping state or county boundaries

state	code	county	code
state	code	county	code

11. Form Prepared By

name/title	Donna M. Ware
-------------------	---------------

organization Anne Arundel Co. Historic Sites Survey **date** 1985

street & number Office of Planning & Zoning **telephone** 301-224-1270

city or town Annapolis, **state** MD

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

return to: Maryland Historical Trust
Shaw House
21 State Circle
Annapolis, Maryland 21401
(301) 269-2438

#7. Continuation sheet, page 2

A beautiful example of the Bungalow style is seen next door at 1395 Odenton Road. It is constructed of rusticated concrete block and has a wrap-around porch which incorporates a turret at the northwest corner.

There are two churches of survey quality within the Odenton Survey District. The Bethel M. E. Church at Waco and Becknel Avenues is a simple rectangular building constructed of rusticated concrete block. It was built in 1917 when the congregation was forced to move from a small frame church that was within the boundaries of the developing Fort Meade complex. The same story holds for the Epiphany Episcopal Church which was built in 1918 at Odenton Road and Morgan Road.

The old Odenton Elementary School, originally known as the Academy, at 1361 Odenton Road, was built in 1892. It is a rectangular two-story structure with the gable end forming the principal facade. It has been altered for use as apartments.

The Odenton Volunteer Fire Company, formed in 1931, used Silver's Warehouse, at the northwest corner of Odenton Road and Morgan Road, as their first fire station. The warehouse, located just south of the Annapolis and Elkridge Railroad (later the Washington, Baltimore and Annapolis Railroad), was used as storage for Silver's Store which once stood adjacent to it.

The Odenton Masonic Temple is one of the largest and most distinctive buildings in the Survey District. Built in 1912, it is a frame, rectangular structure measuring 5 bays by 3 bays. It is covered by a gable roof, distinguished by wide, flared eaves. The offset entrance on the facade is embellished by an elaborate Georgian Revival architrave.

The present Kiwanis Community Center at 1363 Watts Avenue was built in 1925 as the Junior Masonic Order Hall. It is constructed of rusticated concrete block and has a pyramidal roof. A cornerstone, placed in the northwest corner of the building, records the dates of "1895" and "1925." The year 1895 is presumably the year in which the Junior Masons order was organized.

The Citizens State Bank, built in 1917, is a Neo-Classical influenced building, located at 1402 Odenton Road. It faces east toward the Pennsylvania Railroad tracks and is a small square structure constructed of grey rusticated concrete block with contrasting lighter grey rusticated concrete block quoins and a belt-course. The principal entrance on the east elevation is marked by sidelights, a transom and a pediment over the doorway.

-
1. Interview with Catherine O'Malley, May 1, 1984.

#8. Continuation sheet, page 2

(Neither the school nor the church mentioned above is still standing.) The Postmaster was Jacob Watts. He and George M. Murray were the two merchants in town. The Agent for the Railroad (Baltimore and Potomac) and Express was George E. Creider. The community physician was O. Tydings, and the County Commissioner was Allen Warfield.

The oldest standing structure in Odenton is the George M. Murray House at 1390 Odenton Road (Route 677). According to Catherine L. O'Malley, town historian, the Murray House was built in 1873. The rear wing accommodated George Murray's store. To the east, George Murray constructed a tomato canning house in the late 19th century. The enterprising Murray tore it down in 1928 to make way for his new business, a coal yard, which operated from 1928 to 1940.

The Watts House at 1401 Odenton Road was begun in 1881 and has had several additions, resulting in an eclectic blend of architecture. It is not known whether this house was used as a hotel or boarding house, but its size and location at the railroad crossroads strongly support this theory.

Odenton's development was again affected by the construction of another railroad, the Baltimore and Washington Electric Railroad. Begun in 1902, the line paralleled the Baltimore and Potomac Railroad (Pennsylvania Railroad), intersecting the Annapolis and Elkridge line east of the Baltimore and Potomac intersection in Odenton. The Baltimore and Washington combined with the Annapolis and Elkridge (then known as the Annapolis, Washington and Baltimore Railroad) under the name of the Washington, Baltimore and Annapolis Railroad. By 1908, the Washington, Baltimore and Annapolis was providing electric rail service between all three cities.

The construction of Fort Meade in 1917 caused the displacement of many farmers, merchants, public and private enterprises. The War Department acquired 19,000 acres of land west of Odenton, involving over 600 land transactions. Many people relocated in Odenton. Two church congregations moved to Odenton and erected church buildings in 1917 and 1918. They are still standing: Bethel M. E. Church (present YWCA) at 433 Waco Street (2nd Avenue) and the Epiphany Episcopal Church at 1419 Odenton Road. The Citizens State Bank, now abandoned, at 1402 Odenton Road, was constructed in 1917 with the hopes of tapping a new market of investors in Odenton and at the nearby Fort Meade.

AA-869 ODENTON SURVEY DISTRICT

Key

Contributing Resources:

A - Excellent

B - Good

C - Mid-level


D - Minimal

Non-Contributing - E

Scale: 1" = 450'



AA-869



Odenton, MD
 USGS 7.5 Minute Series
 Scale 1:24,000
 1957; Photorevised 1979

AA-869
 Odenton Survey District
 Odenton Rd. (Rt. 677) and
 vicinity



AA-869

Odenton Survey District

Anne ARundel Co. Md.

Photo: D. Ware, 2/84

View of Watts House, across Penn

RR tracks. looking S. W.



AA-869

Odenton Survey District

Anne Arundel Co., Md.

Photo: D. Ware, 2/84

Penn. RR tracks, looking N. from

Odenton Rd.



AA. 860

Odenton Survey District

Anne Arundel Co., md.

Photo; D. Ware, 2/84

¹ Penn. RR tracks, looking N. from
Odenton Rd.



AA-869

Odenton Survey District

Anne Arundel Co., Md.

Photo: D. Ware, 2/84

Penn RR facility, S. elev.



AA-869

Odenton Survey District

Anne ARundel Co.,Md.

Photo: D. Ware, 2/84

1391 Odenton Rd. - N. elev.



AA-869

Odenton Survey District

Anne Arundel Co. Md.

Photo: D. Ware, 2/84

1367 Becknel (Watts) Ave,

N. eley.



AA-869

Odenton Survey District

Anne Arundel Co., Md.

Photo: D. Ware, 2/84

1385 Odenton Rd, - N. elev.



AA-869

Odenton Survey District

Anne Arundel Co., Md.

Photo: D. Ware, 2/84

1381 Odenton Rd., N. Elev.



AA-869

Odenton Survey District

Anne Arundel Co., Md.

Photo: D. Ware, 2/84

Masonic Temple, 1367 Odenton Rd.

rear, S. elev.



AA-869

Odenton Survey District

Anne Arundel Co., Md.

Photo: D. Ware, 2/84

Masonic Temple, 1367 Odenton Rd.

Entr. ↖ N. Elev.



AA-869

Odenton Survey District

Anne Arundel Co., Md.

Photo: D. Ware, 2/84

Jr. Order of Masons Lodge -N.

elev.



AA-869


Odeon Survey District

Anne Arundel Co. MD

Photo: B. Ware, 1984

Masonic Temple,

facade, ~~North~~ elev.



AA-869

Odenton Survey District

Anne Arundel Co., Md.

Photo: D. Ware, 2/84

1366 Odenton Rd. - S.W. elev.



AA-869

Odenton Survey District

Anne Arundel Co., Md.

Photo: D. Ware, 2/84

1359 & 1361 Becknel(Watts)Ave.

looking S.



AA-869

Odenton Survey District

Anne Arundel Co., Md.

Photo: D. Ware, 2/84

looking S.E. on Odenton Rd., old

Odenton Elem. Sch. in foregrd.



AA-869

Odenton Survey District

Anne Arundel Co., Md.

Photo: D. Ware, 2/84

1375 & 1371 Odenton Rd., looking
S. E.



AA-869

Odenton Survey District

Anne Arundel Co., Md.

Photo: D. Ware, 2/84

Bethel M.E. Church, 433 Waco St.

side ↖ N. eley.



AA-869

Odenton Survey District

Anne Arundel Co., Md

Photo: D. Ware, 2/84

Bethel M.E. Church, 433 Waco St.,
facade, W. elev. & side & S. =



AA-869

Odenton Survey District

Anne Arundel Co., Md.

Photo: D. Ware, 2/84

Epiphany Epis. Church, 1419

Odenton Rd.. W. elev.



AA-869

Odenton Survey District

Anne ARundel Co., Md.

Photo: D. Ware, 2/84

Epiphany Epis. Church, 1419

Odenton Rd S elev



AA-869

Odenton Survey District

Anne Arundel Co. , Md.

Photo: D. Ware, 2/84

Citizens State Bank, s. elev.



AA-869

Odenton Survey District

Anne Arundel Co., Md.

Photo: D. Ware, 2/84

Citizens State Bank, facade, E.

elev. and side - N. elev.

9



AA-869

Odenton Survey District

Anne Arundel Co., Md.

Photo: D. Ware, 2/84

Citizens State Bank, 1402 Odenton

Rd. - entrance - E. elev.



AA-869

Odenton Survey District

Anne Arundel Co., Md.

Photo: D. Ware, 2/84

1st Fire House, 366 Morgan Rd.

S. elev.



AA-869

Odenton Survey District

Anne Arundel Co., Md.

Photo: D. Ware, 2/84

Geo. M. Murray House, 1390

Odenton Rd. - South elev.